


G^0 Backward Angle Accelerator Preparations

Joe Grames (G^0 Project Coordinator)

- Infrastructure & Planning
- Scope of Work
- CEBAF Preparations
 - Polarized Source
 - Injector
 - Accelerator
 - Hall C
- 2006 Program

Hall C Conduct Of Operations (COO) & Resource Allocation



Scope of Work

Sep. '05 - Coordinated preparation begins

Oct. '05 - Extended Hall C down begins

Jan. '06 - Accelerator Shutdown

Firm Schedule

Mar. 15 - Apr. 2, Commissioning Period
(following long down)

Apr. 3 - Apr. 29, High Q^2 Run (687 MeV)
(3-halls, all polarized)

Tentative Schedule

Jul. 21 - Sep. 1, Low Q^2 Run (362 MeV)
(1-pass, 1-linac, 2-halls)

Sep. 22 - Dec. 22, High Q^2 Run (687 MeV)

CEBAF Preparations - Polarized Source


Laser

Ti:Sapphire (780 nm)
 $f \sim 499$ MHz

Parity Quality Laser Setup
 G^0 Helicity Sequence

G^0 Ownership of InjDAQ

Pockels cell alignment
IA intensity FB
Rotatable $\frac{1}{2}$ -waveplate
Insertable $\frac{1}{2}$ -waveplate



Polarized Source
Gun2 (or Gun3)


Anodized
SL-GaAs

$P > 80\%$

$I_{\text{beam}} \sim 80 \mu\text{A}$

CEBAF Preparations - Polarized Source


Polarization ~86%



Lifetime ~130 C

$A = 20 \mu\text{A}$
 $B = 5 \mu\text{A}$
 $C = 80 \mu\text{A}$


~10 C/day



CEBAF Preparations - Injector

Helicity correlated position differences generated at the source are suppressed by natural process of adiabatic damping (ratio of transverse to longitudinal momentum becomes smaller as beam is accelerated).

- “Matching” the beam emittance to the accelerator acceptance achieve damping.
- A poorly matched beam may result no (or larger) position differences.
- Matching in the accelerator proper (linacs & arcs) routinely demonstrated.
- Matching in the injector has been an arduous, long (~2 year) process.



Experiment	Photocathode	Charge Asymmetry at Target		Position Difference at Target	
		Spec	Achieved	Spec	Achieved
HAPPEX-I	Strained	1 ppm	0.4 ppm	10 nm	10 nm
HAPPEX-He	Superlattice	0.6 ppm	0.08 ppm	3 nm	3 nm
HAPPEX-H	Superlattice & Strained	0.6 ppm	2.6 ppm	2 nm	8 nm
HAPPEX-He (2005)	Superlattice	0.6 ppm	?	3 nm	4 nm (x) 17 nm (y)
HAPPEX-H (2005)	Superlattice & Injector Match	0.6 ppm	0.2 ppm	2 nm	1 nm (x) 1 nm (y)

GO requirements

=>

<2 ppm

<40 nm

CEBAF Preparations - Injector

Helicity Magnets

Will replace PZT mirror
(electron beam vs. laser beam)

4 magnets =>
position (x,y) & angle (x',y')



Linear, Independent, Electrically isolated
Fast rise time & correlated with helicity pattern
Orbit set in each helicity state (PZT set in one helicity state)

Resolution presently 100 nm/DAC step (at 5 MeV)
New DAC to be installed => 10 nm/DAC step (at 5 MeV)

CEBAF Preparations - Accelerator

PZTBooster Concept:

Injector matching process

- Time consuming
- Small amplitude signal

Helicity Magnets in new "Optics Mode"

- Runs triggered to BPM acquisition system
- Large amplitude signal

Goal:

- Streamline injector matching
- Improve accuracy of result
- Allow for rapid confirmation

CEBAF Preparations - Accelerator

Planning for accelerator proper (after injection & before extraction) is mainly directed toward the very low energy run, which exists on the tentative schedule.

To conserve electrical power the north linac will be **ON** and the south linac will be **OFF** (so that ARC1 can transport the beam).

We will retain cavities in SL for energy feedback only

Test of half pass extraction in December OK; require shielding in the extraction line to improve orbit control.

Tentative schedule A & C run together in this configuration:

We will extract to 5th pass line and use one RF separator

Test of 2-beam extraction in December demonstrated feasibility.

CEBAF Preparations - Hall C

Accelerator division support leading to installations/modifications:

- Install Moller kicker to allow high current polarimetry
- Move Moller quadrupole to reach low energy polarimetry
- Arrange focussing optics to improve spot size (halo?) control
- Install cryogenics platform to meet safety requirements
- Re-install Halo & GO girder, improve mating to GO spectrometer

Accelerator division supporting preparations/calculations:

- Radiation analysis for beam dump at low energy, high current

Efforts now shifting toward checkout, beam delivery, commissioning plans, operations, & safety.

2006 Program

Presently in the Winter shutdown

Hall C work continues on schedule (Gaskell reports)

January activities

- Polarized source prepared

- Laser setup

- PQB source commissioning

- 5 MeV helicity magnets checkout

- Injector Setup & Matching

- Parity Quality Beam setup

- 2-beam extraction test