

Barrel TRT Straw Leak Test

K. McFarlaneHampton UniversityKrakow, 1-Jun-1999



Straw Leak Testing

- This is a bottle-neck in production, at five minutes/straw
- PRR requested automation
- A study with a one-straw and a two-straw manual system gives the time taken for N straws tested manually as (4+N) minutes. If some aspects are automated, this may go to (3.5+0.5N) minutes.



Production per shift

120/shift meets schedule, 240/shift capability is desired

No. of straws tested/cycle	Manual	Automated
1	72	90
2	120	160
4	180	260
8	240	380



Production rates

- Steps are (automated in parentheses)
 - Mount, 0.5 min/straw
 - Pressurize, wait for equilibrium, 3 mins
 - Record trend, 0.5 min/straw (0.5 min/cycle)
 - End effects, 1 min/cycle (0.5 min/cycle)



Status

- Multiple-straw leak tester under development
- Steps (currently manual) to be automated
 - Control of sealing actuators
 - Adjustment of test pressure (200 mbar)
 - Control of straw close-off valve
 - Timing of cycle
 - Recording of differential pressure trend



Steps to automation

- Pneumatic operation of all valves (done)
- Electrical operation of pneumatics (done)
- Logic level control of electrical operation
- Computer-generated logic sequence
- Computer acquisition of parameters, with display for operator
- Recording in database




Development steps

- Two-straw manual system (done)
- Two-straw system, electrical control (done);
 logic level control minor step
- Four-straw system, logic level control (human recording)
- Four-straw system, computer control and pass/fail indication
- Four-straw system, database input, SPC




Two-straw, electrical control






Leak Test Control Box



Note: designed to operate 8 straw system



Pneumatic Schematic





Schedule

- Two-straw system done
- Four-straw with computer control, recording August, 1999.